

CMS Silicon Tracker Status and Plans

On behalf of the US Tracker Group

Joe Incandela

University of California Santa Barbara

US CMS Silicon Tracker Level 2 Manager



Overview

- Summer Pilot Production:
 - US tracker group found and helped to remedy a few residual issues
 - Transport damage (discussed at Lehman review in May)
 - Broken traces on hybrid cables
 - Common mode noise induced by leaky strips
- Component availability:
 - Significant flows began this summer but had to be stopped.
 - Hybrids halted in September, restarted October.
 - Sensor quality improving, deliveries well-underway, but some concerns remain
- US Production readiness
 - For Modules: Several innovations with productivity gains
 - UCSB now capable of ≥ 15 modules/day (require 9/day for TOB)
 - FNAL to be upgraded to match.
 - Rods: still on schedule to be ready for peak production in early 2004




Recent Changes and Additions

- Improving parts flow
 - US CMS will wirebond and thermal-cycle/pulse-test all Tracker Outer Barrel (TOB) and Tracker End Cap (TEC) hybrids (~11,000)
 - Relieves CERN bottleneck, improving hybrid flows
 - U. Rochester has been certified for ST sensor probing
 - Relieves potential bottlenecks in sensor deliveries to the US
- US group to be involved in Tracker End Cap (TEC) production:
 - Help to maintain quality and schedule of entire tracker project
 - Refined electronic test stands, developed uniform testing procedures, established cross-calibrations
 - Asked to review fabrication centers: consult and assist
 - To prepare for fabrication up to 2000 TEC modules
 - Backup Tracker End Cap production centers, provide expertise and critical review of overall TEC designs and procedures.



Spring/Summer Pilot Production



- 103 TOB modules produced in US
 - 14 April, 8 May, 17 June, 24 July, 40 August
 - Have produced only a handful since August due to various problems
- FNAL and UCSB have produced roughly equal numbers
 - Very high quality.
 - All are within mechanical specifications.
 - Production induced fault rate well under 1% and falling!



CMN Problem

- ~20%* modules have common mode noise (one chip)
 - Built with very early ST sensors
- Correlated w/increased bias current w.r.t. QTC probing
 - UCSB study ruled out hypothesis of mishandling in US
- High noise 1-4 channels \Rightarrow source of CMN for chip
 - No obvious associated damage in visual inspection
- Problem generally appears at the first module test
 - 1 module at FNAL developed problem during module long-term thermal cycle testing

*The sampling of sensors was slightly biased toward high-fault rate sensors. Almost all from old batches of type 2 sensors. Actual rate is around 10% for early sensors.



IV Test Results

Probed Current @ UCSB (400 V) – QTC Measurement (400 V)

Sensors	> 2 μA	> 5 μA	>10 μA	>20 μA	>100 μA	< -2 μA	<-5 μA	<-10 μA
OB2 ('00-01)	15%	9%	8%	5%	1%	8%	3%	1%
OB1 ('00-01)	6%	3%	3%	3%	3%	3%	0%	0%
OB2 ('02)	3%	3%	0%	0%	0%	2%	2%	0%

- An increase greater than 5 μA can cause CMN
- *Much better results with newer OB2 sensors (2002)*
 - Factor of ~4 decrease in the rate of higher (and lower) current measurement at UCSB relative to old OB2 sensors
- *A batch of 2003 sensors are now en route*





CMN problem and ST sensors

- UCSB Study
 - IV curves did not change after module fabrication
 - 4 of 5 modules with a **high** current sensor had CMN problems
 - 19 of 20 modules with a **low** current sensors had no problems
- The Situation
 - Probing centers selecting ST sensors with low total current
 - 75% of all delivered sensors pass a cut of $1.5 \mu\text{A}$
 - All selected sensors expected to make good modules **but**
 - » Delivery inadequate for schedule
 - » IV measurements alone saturate QA capacity
 - Steering Committee actively pursuing all options
 - Working with ST to improve quality to increase yield and increase production
 - Investigating other vendors



Hybrid Problem

- Cable brittle at connector solder pads
 - Differential data output lines break
- Reported by US on Sept. 4
 - Production was halted that week.
 - Protective stiffener designed and studied by US and vendor
 - Production re-started Oct. 20
- Current schedule looks good
 - 100 TIB hybrids delivered early Nov.
 - 500 hybrids per week as of late Nov.
- 4000 hybrids were in production when problem was discovered
 - 1000 throwaways and 3000 retrofits
- Barring new problems, sensors will replace hybrids as the limiting factor by January.






Overview of Production Lines

- Improvements, Readiness, Current Capacity
 - Hybrid Thermal Cycler/pulser
 - 1st stand completed, validated and online at UCSB
 - 2nd started, to be online at FNAL by early February
 - Gantry:
 - Stereo and 6 chip module production has been started
 - Problem with the gantry robot has been isolated and fixed
 - Can now do plate surveys off the gantry
 - Wirebonding
 - Full automation in effect
 - Module Testing
 - 90% of all necessary equipment installed and online
 - Full capacity LT test in Wien Cold Box
 - Rod Assembly, Test, LT test on schedule
- Near term Planning
 - A **Sustained** high throughput production run
 - Adding production capacity and manpower





Front End hybrids delivery




Accelerate hybrid delivery with US help: CERN - FNAL - UCSB = 40% - 30% - 30%



Hybrid Thermal Cycler & Pulser



- Now fully commissioned
 - Substantial effort!
- 40 minutes to cycle 4 hybrids
 - Finds shorts/opens
- Capacity $\geq 28/d$ per stand
 - UCSB stand already online
 - FNAL stand will be online by Feb.







Assembly Plates & Tools

- *Plates work “right out of the box”*
 - 4 fully commissioned R-phi plates
 - 1 prototype R-phi assembly plate (could be used if needed)
 - 1 fully commissioned Stereo plate

3 μm alignment for 1st 3 modules!
- *New pickup tools*
 - *More reliable and accurate*



New Hybrid bridge



New hybrid and sensor pickup tools




Other Enhancements

- Gantry 3rd position problem fixed
 - Limited work area usage to 67%
- Surveying/DB
 - Recently automated full plate survey on OGP
 - Much faster than the gantry!
 - Macros compare the survey results to nominal values
 - Each position on each plate treated individually.
 - Allows module production on gantry all day.

Commercial high precision ($< 1 \mu\text{m}$) **automated** measuring machines (OGP) with pattern recognition at FNAL and UCSB


- Provides independent survey of modules





Wirebonding


UCSB TOB 4 chip module
bond time 5 minutes:
Average of 1 channel
needing to be re-bonded
every 7 modules



- K&S automatic wirebonders
 - Currently 4 machines: 3 at FNAL and 1 at UCSB
 - FNAL: will likely need 1-2 for other projects much of the time
 - Need backup at UCSB
 - Plan to buy a used K&S 8060
 - smaller work area but otherwise identical
 - more common (available and cheaper).



Long Term and Rod Testing




- Complete set of electronics ready to test single rods
 - Test box provides dry, dark, and electrically isolated environment
 - Uses Rod LT chiller for cooling
- First rod in US fully assembled
 - Took approximately 2 hours!
- Noise under control!

• Multi-rod Long Term test stands

- 1st Freezer moved from Rochester to Fermilab this past October.
- 2nd to be delivered to UCSB in December.


• Module Long Term test stand (Wien Boxes)

- All functionalities demonstrated
 - Cold box fully instrumented
 - 10 module capacity
 - Conducted backplane pulse tests
- LT test ALL modules with full readout of temperatures and currents






Probing at Rochester (see talk by S. Korjenvski)



- ✓ **Hardware** is in place and operational.
- ✓ **Software** is working as well, - test results are consistent with other testing centers
- ✓ **Qualified**





Capacity and Plans

- Current capacity
 - UCSB current capacity ≥ 15 modules per day
 - Over 12 requires shortening LT test to 12 hours
 - With expected improvements we can extend this
 - Requires 2nd wirebonder for backup
 - FNAL current capacity 8 modules per day
 - Limited by Wien box but MUX received
 - Should reach 12 per day soon
 - Will modify several setups and procedures to match UCSB
- Goals:
 - 15 per site in a normal work day
 - 21 per site in a slightly extended day
- *Near term: to produce ~100 modules in 1 week when hybrids arrive.*



Contingencies

- Enhanced Capacity

30 modules/day \Rightarrow 6375 per year (with 15% downtime)

42 modules/day \Rightarrow 8925 per year (with 15% downtime)

TOB total is 5500


- Several potential benefits

- Contingency for a compressed TOB production schedule.
- Backup for TEC production lines.



TOB Module Schedule


TOB Modules





TEC Module Schedule

TEC Modules





Additional Costs

- 465k\$ + 250k\$ contingency
 - Additional hybrid bonding and testing at FNAL
 - Enhancements to allow faster TOB production + some TEC Production.

	Cost (k\$)	Contingency (k\$)
Hybrids equipment	20	10
Hybrids Labor	130	40
Wirebonding Upgrades	90	40
Gantry Upgrades	50	25
Module Labor	110	110
Transport & Travel	65	35
Total	465	260



Schedule and Outlook

- Schedule
 - CERN schedule shows most modules complete by end of 2004
 - CERN management is committed to this
 - To leave as much time as possible for commissioning
 - Nevertheless, this is an aggressive schedule
 - Completion by end of US CMS FY05 is not yet at risk:
 - 20 months from January 2004.
 - Components must be available in this period!
 - US capacity adequate for much shorter production period.



Conclusions

- Many productivity improvements
 - Gantry 3rd position problem fixed
 - Automated surveys on OGP
 - Automated wirebonding programs
- Many Significant Achievements
 - First rod assembled and tested – good results
 - First stereo modules
 - Wien box fully instrumented with backplane pulsing
 - 4-hybrid test stand fully functional
 - First LT Rod stand delivered to FNAL
 - Rochester qualified for sensor probing
- We'll increase capacity and production at low cost
 - Schedule contingency
 - Assist the overall tracker project





Additional Information

- Gantry Data – Sensor alignments
- Sources of faulty channels
- Common Mode Subtracted Noise
- UCSB Gantry Hardware Improvements
- *Gantry 3RD Position Problem*
- Modules Produced with Final Hybrids
- Vacuum Rod Assembly Tools



Gantry Data – Sensor alignments




UCSB results shown, FNAL results are equivalently good



Faulty Channel Sources

- Fault Sources (excluding cable breaks and CMN)
 - Hybrid-0.011%
 - Sensor (in DB)-0.33%
 - Sensor (not in DB)-0.26%
 - Either high noise and/or visible sensor damage
 - Bonding-0.037%
 - Mostly due to early pitch-adaptors (RMT).
 - No problems seen with production pitch-adaptors (PLANAR).
 - Testing-0.074%
 - Mostly due to an early problem which has been alleviated
- Total faults – 0.712%






Common Mode Subtracted Noise

25 ADC

6.5 ADC



Chips with CMN in UCSB modules

Common mode subtracted noise in blue

**For majority of modules with problems, the CM subtraction is imperfect.
7 of 12 have >2.0 ADC noise
3 of 12 have more than twice the usual noise**



US Gantry Hardware Improvements


**1. U motor mounting bracket replaced:
Z and U axes orthogonal
to base plate**




2. New Support pads



**3. Assembly plate
underside modified**





4. New Teflon topside







Gantry 3RD Position Problem



- Problems at all gantry centers in a specific region of gantry work area.
- Reduced CMS production capacity by 25-33% !!
- Russell Taylor (UCSB) pinpointed the problem and came up with a fix
 - Studies showed a **strip in the gantry Y axis between the 3rd and 4th rows of the calibration file** where counting errors occurred **independent of calibration grid size** (indicating a software or memory problem)
- We reported the problem to the OEM and they were able to update their software to remove the problem.







Modules Produced with Final Hybrids



- First Stereo TOB module made!
 - 3 TOB stereo module produced in total
 - All well within specs mechanically and all Grade A
 - Kapton circuit was missing a trace for bias. We made it by hand with Ag Epoxy.
 - One chip has dead pipeline column
 - Found to be dead prior to module production
- 2 TOB 6-chip R- Φ module produced (first module of this kind produced!!)
 - Both Grade A
- 1 TOB 4-chip R- Φ module with final hybrid built
 - Grade B due to known sensor faults





Vacuum Rod Assembly Tools





Wien Module LT Test

- All functionalities demonstrated
 - Cold box fully instrumented
 - 10 module capacity
 - Conducted first backplane pulse tests
- LT test ALL modules with full readout of temperatures and currents



Module 1025 Backplane test